TOWN OF RIVERHEAD PURCHASING OFFICE
BID TAB SHEET

BID NAME:			Installation of Water Mains and Appurtenances at G&Z Retirement Community, Middle Road										
BID OPENING DATE:			June 25, 2020										
COMPANY:				Merrick Utility Assoc. Inc.		Alessio Pipe & Construction Co. Inc.		Adjo Contracting Corp.		Bancker Construction Corp.		G&M Earth Moving Inc.	
CONTACT:				Frank DiOrio		Robert J. Alessio		Joseph Bongiorno		Phillip M. Beyer		Ralph Coffill	
PHONE #:				631-249-2560		631-423-0234		631-589-0800		631-582-8880		631-567-0120	
BID BOND PROVIDED?				Yes		Yes		Yes		Yes		Yes	
ITEM	**QTY**	**UNIT**	**DESCRIPTION**	**UNIT PRICE**	**NET PRICE**	**UNIT PRICE**	**NET PRICE**	**UNIT PRICE**	**NET PRICE**	**UNIT PRICE**	**NET PRICE**	**UNIT PRICE**	**NET PRICE**
1 A	20	LF	Furnish & Install 6" Cement-Lined Ductile Iron Water Main, Push-on Joint, Special Class 52	$ 30.00	$ 600.00	$ 40.00	$ 800.00	$ 20.00	$ 400.00	$ 54.40	$ 1,088.00	$ 20.00	$ 400.00
1B	510	LF	Furnish & Install 8" Cement-Lined Ductile Iron Water Main Including Restoration. Push-on Joint, Special Class 52	$ 71.00	$ 36,210.00	$ 80.00	$ 40,800.00	$ 208.00	$ 106,080.00	$ 60.00	$ 30,600.00	$ 92.00	$ 46,920.00
2	2000	LBS	Furnish & Install Mechanical Joint C.L.D.I Fittings. (Quantities based on C153 weights)	$ 1.00	$ 2,000.00	$ 1.00	$ 2,000.00	$ 1.00	$ 2,000.00	$ 1.00	$ 2,000.00	$ 1.75	$ 3,500.00
3A	2	UNIT	Furnish & Install 6" Mechanical Joint Gate Valve including Valve Box and Restraining Glands.	$ 1,800.00	$ 3,600.00	$ 3,000.00	$ 6,000.00	$ 925.00	$ 1,850.00	$ 2,000.00	$ 4,000.00	$ 1,000.00	$ 2,000.00
3B	2	UNIT	Furnish & Install 8" Mechanical Joint Gate Valve including Valve Box and Restraining Glands.	$ 2,200.00	$ 4,400.00	$ 4,000.00	$ 8,000.00	$ 1,400.00	$ 2,800.00	$ 2,500.00	$ 5,000.00	$ 1,400.00	$ 2,800.00
3D	1	UNIT	Furnish & Install 12" Mechanical Joint Gate Valve including Valve Box and Restraining Glands.	$ 3,475.00	$ 3,475.00	$ 6,000.00	$ 6,000.00	$ 2,600.00	$ 2,600.00	$ 4,000.00	$ 4,000.00	$ 2,500.00	$ 2,500.00
4A	2	UNIT	Furnish & Install Hydrant (Mechanical Joint Inlet) with Rods and Restraining Glands.	$ 7,800.00	$ 15,600.00	$ 8,000.00	$ 16,000.00	$ 5,800.00	$ 11,600.00	$ 7,000.00	$ 14,000.00	$ 6,000.00	$ 12,000.00
4B	1	UNIT	Relocate Hydrant Assembly	$ 6,000.00	$ 6,000.00	$ 3,000.00	$ 3,000.00	$ 4,700.00	$ 4,700.00	$ 5,000.00	$ 5,000.00	$ 6,000.00	$ 6,000.00
5	540	LF	Disinfecton, De-Chlorination, Flushing & Testing of Water Mains.	$ 1.00	$ 540.00	$ 1.00	$ 540.00	$ 7.00	$ 3,780.00	$ 2.00	$ 1,080.00	$ 1.00	$ 540.00
8D	1	UNIT	Cut-in to Existing 12" Water Main.	$ 12,400.00	$ 12,400.00	$ 10,000.00	$ 10,000.00	$ 13,700.00	$ 13,700.00	$ 20,000.00	$ 20,000.00	$ 12,500.00	$ 12,500.00
9	540	LF	Backfill & Trench Compaction.	$ 1.00	$ 540.00	$ 1.00	$ 540.00	$ 1.00	$ 540.00	$ 4.00	$ 2,160.00	$ 1.00	$ 540.00
10A	20	SY	Repaving Roadways (Town & Village Roadways) incl. permitting, saw-cutting, removals, disposals, installation of base, binder, and wearing course, sealing and re-striping.	$ 20.00	$ 400.00	$ 20.00	$ 400.00	$ 535.00	$ 10,700.00	$ 20.00	$ 400.00	$ 700.00	$ 14,000.00
26A	1	n/a	Moving/re-mobilization Fee (fixed price)	$ 2,500.00	$ 2,500.00	$ 2,500.00	$ 2,500.00	$ 2,500.00	$ 2,500.00	$ 2,500.00	$ 2,500.00	$ 2,500.00	$ 2,500.00
30A-S	6	UNIT	Furnish & Install new 1" water service (short side) including new corporation stop, copper piping, curb stop with box and meter pit.	$ 2,000.00	$ 12,000.00	$ 2,400.00	$ 14,400.00	$ 3,800.00	$ 22,800.00	$ 2,500.00	$ 15,000.00	$ 4,100.00	$ 24,600.00
30A-L	4	UNIT	Furnish & Install new 1" water service (long side) including new corporation stop, copper piping, curb stop with box and meter pit.	$ 2,225.00	$ 8,900.00	$ 2,800.00	$ 11,200.00	$ 4,400.00	$ 17,600.00	$ 2,600.00	$ 10,400.00	$ 3,300.00	$ 13,200.00
30R-2	5	UNIT	Furnish & Install new 1" water service (extra-long side) including new corporation stop, copper piping, curb stop with box and meter pit.	$ 2,800.00	$ 14,000.00	$ 4,000.00	$ 20,000.00	$ 6,000.00	$ 30,000.00	$ 2,800.00	$ 14,000.00	$ 5,000.00	$ 25,000.00
			TOTAL BID (Sum of all items):		$ 123,165.00		$ 142,180.00		$ 233,650.00		$ 131,228.00		$ 169,000.00