

Town of Riverhead
Suffolk County, New York

TOWN OF RIVERHEAD
HIGHWAY DEPARTMENT
EXTERIOR OFFICE IMPROVEMENTS
ADDENDUM No. 2
August 6, 2015

Addendum No. 2 is hereby made a part of the Contract Documents of the above project for the Town of Riverhead, Suffolk County, New York and shall be bound with the documents titled:

**TOWN OF RIVERHEAD
HIGHWAY DEPARTMENT
EXTERIOR OFFICE IMPROVEMENTS**

- A. Comments and/or questions from prospective bidders must be submitted in writing and may be submitted to dillingham@townofriverheadny.gov until 4 PM EST, August 20, 2015.
- B. "Exterior Office" shall mean the entire outside of the Highway Department Building including the office, shop and garage.
- C. The Town of Riverhead will remove and replace all electronic equipment and wiring which is located on the exterior of the office and within the work limits.
- D. Item 9. Security for Faithful Performance and Maintenance, Instructions to Bidders:
- Revised the first sentence to read, "The successful bidder will be required to execute a Performance Bond (refer to 10. Contract Security, Conditions of Contracts for specified values) at the signing of this contract."
 - The last sentence was removed.
- E. The revised Itemized Proposal form is attached to this addendum and was modified as follows:
- Second line was revised to read, "Install new 2"x4" pressure treated furring strips spaced at 18" on center on the exterior of the office with 3" thunder bolt pins."
 - Third line was removed.
 - Sixth line was revised to read, "All outside corner posts will be insulated and installed in 20' lengths."
 - Ninth line was revised to read, "Remove any existing gutters, scuppers and leaders where located on porch and entire exterior of office and install new scuppers, gutters and leaders."

- Tenth line was revised to read, “Install PVC coated aluminum metal caps or approved equal as necessary on exterior of office and porch.”
- Eleventh line was revised to read, “Remove two existing light fixtures under porch and install three new fixtures in kind.”
- Twelfth line was revised to read, “Remove seven existing calamine windows. Frame cinder block openings to accept new windows. Install seven Kensington 300 Series double hung vinyl windows with fully insulated frame, triple seal weather stripping, half screens, and low emissivity and argon hi-performance glass or equal. Double seal new windows. Cap window with premium quality scratch and chalk resistant vinyl coated grained aluminum trim. New windows must have lifetime manufacturers’ warranty covering all parts from breakage. Workmanship must be covered for one year.”
- Thirteenth line was revised to read, “Remove debris from each of twenty existing vinyl windows. Reframe and reinstall twenty existing vinyl windows. Insulate, cap, caulk and seal. “
- Last line was revised to read, “All workmanship must be covered for one year.”

This ADDENDUM No. 2 for the HIGHWAY DEPARTMENT, EXTERIOR OFFICE IMPROVEMENTS does not change the bid due date. Bids will still be received by the Town of Riverhead in the Office of the Town Clerk, Riverhead Town Hall, 200 Howell Avenue, Riverhead, New York, until 4:00 pm, August 27, 2015, and publicly opened and read aloud at 11:00 am, August 28, 2015.

EXTERIOR OFFICE IMPROVEMENTS
HIGHWAY DEPARTMENT
1177 OSBORN AVENUE
TOWN OF RIVERHEAD
July 17, 2015
Revision 1 - August 6, 2015

Item No.	Description	Unit	Estimated Quantity	Unit Cost	Total Price
	Remove all of the existing T-111 siding and furring strips on the exterior of the office.				
	Install new 2"x4" pressure treated furring strips spaced at 18" on center on the exterior of the office with 3" thunder bolt pins.				
	Install a factory D-7 starter strip around the office to accept the proposed siding.				
1	Install approximately 40 sheets of D-7 foam back exterior portfolio in 16' horizontal siding panels on office exterior.	SF	4000		
	All outside corner posts will be insulated and installed in 20' lengths.				
	Light blocks and split blocks shall be installed where needed in conjunction with siding installation.				
	Remove existing soffits located beneath main entrance porch. Install furring strips and subsequently approximately three sheets of vinyl center-vent soffits.				
	Remove any existing gutters, scuppers and leaders where located on porch and entire exterior of office and install new scuppers, gutters and leaders.				
	Install PVC coated aluminum metal caps or approved equal as necessary on exterior of office and porch.				
2	Remove two existing light fixtures under porch and install three new fixtures in kind.	Ea.	2		
3	Remove seven existing calamine windows. Frame cinder block openings to accept new windows. Install seven Kensington 300 Series double hung vinyl windows with fully insulated frame, triple seal weather stripping, half screens, and low emissivity and argon hi-performance glass or equal. Double seal new windows. Cap window with premium quality scratch and chalk resistant vinyl coated grained aluminum trim. New windows must have lifetime manufacturers warranty covering all parts from breakage. Workmanship must be covered for one year.	Ea.	7		
4	Remove debris from each of twenty existing vinyl windows. Reframe and reinstall twenty existing vinyl windows. Insulate, cap, caulk and seal.	Ea.	20		
	All workmanship must be covered for one year.				
TOTAL					